


Prospects for Nuclear Power worldwide & Learnings from past and on-going Project Implementation

Energy Day Congress
Helsinki, Hilton Kalastajatorppa
October 20th, 2009

Nuclear power production is currently making up app. 15% of the worldwide electricity production.


Worldwide Electricity Production 2007 [TWh]



Source: IEA, Pöyry


Utilities and governments are planning on investing in new nuclear power plants all over the world.

Nuclear power plants worldwide – existing, under construction and under development.



Pöyry assumes the total installed nuclear capacity to reach 600 GW by 2030.


Scenarios of demand for nuclear power capacity worldwide



- Several sources are providing forecast scenarios regarding the development of nuclear energy.
- Pöyry has developed its nuclear scenario based on its unique market intelligence and experience-based understanding of worldwide trends of energy supply and consumption.
- Pöyry's reference assumption for nuclear power generation in 2030 ties in with the average of other relevant forecasts.

Based on lifetime extensions of 186 GW for existing nuclear capacity, new-build's of 280 GW are assumed by 2030.


Estimated demand for new-build nuclear power plants



- Various reactor types will be applied for “new build’s” worldwide, unit sizes of 600-1600 MW are under consideration.
- Lifetime-extensions are expected to contribute almost one third of the nuclear capacity foreseen for 2030
- It is assumed that the on-going financial crisis will have only slight impacts in the short run by creating additional uncertainty for investment.


In order to cope with expected demand, the nuclear power industry has to cope with similar growth rates as for the last investment cycle

Historical and projected rate of capacity additions for NPPs worldwide



It is estimated that more than half of the nuclear power plants worldwide have been implemented with a cost overrun and/or delay.

**Cost overruns for NPP in the past
(in the respective currencies)**




- Massive cost overruns have been experienced in the past, which create a major risk for the future development of nuclear power
- The most cited reasons for cost overruns are
 - Changing requirements from the licensing side
 - Lack of standardization and front end engineering
 - Overly ambitious targets of the owner
- Although AECL of Canada (Candu reactors) experienced a record cost overrun in their Darlington project, all of their seven overseas projects between 1997 and 2007 were built in budget and on time. As reasons for this, CANDU mentions
 - High standardization
 - Local Canadian supply chain for critical items
 - Favorable regulatory environment
- Also the French nuclear power plant fleet was implemented without major delays or cost overruns, mostly due to a highly standardized design

Problem areas for nuclear power plant implementation are general for large and complex infrastructure projects.

Key problems in implementation of new nuclear power plants

Build before design completion	<ul style="list-style-type: none"> • „design as you go“ • Bid to win mentality • Misalignment of civil construction and mechanical erection 	Unstructured problem identification, resolution and documentation	<ul style="list-style-type: none"> • Lack of well-defined processes • Silo protectionism (often many silos even w/in groups) No “one project one team” mentality. • Cultural barriers within the team
Inadequately defined scope	<ul style="list-style-type: none"> • Due to incomplete design • inadequate contract provisions • No benchmark to manage the project. 	Marginal owner involvement	<ul style="list-style-type: none"> • Rely on Contractor (deemed expert) • Good engineers presumed to be good managers • Weak executive involvement
Custom design	<ul style="list-style-type: none"> • Contractor supply-chain-management not in line with engineering • No availability of standard designs 	Ineffective contract administration	<ul style="list-style-type: none"> • Vague contract terms, difficult to track and oversee • Marginal dedicated oversight of contract performance (Contrast
Poor schedule integration	<ul style="list-style-type: none"> • Construction builds by “Area” - Big stuff in first • Construction dominance in the scheduling process • Limited detailed coordination interfaces 	Lack of risk identification and management	<ul style="list-style-type: none"> • Risk management procedures not existing or not adequate • No risk mitigation measures defined ex-ante • Reactive vs. Proactive approach to failures

Four areas are identified to address the problems experienced in implementing nuclear power plants.



Three basic types of implementation methods are distinguished according to the number of contracts and the division of risk between owner and contractors.

Three general approaches for project implementation

- EPC-turnkey** – single contractor/point of responsibility
 Implementation risks included in contract and covered by liquidated damages.
 Open book procedure optional for transparent pricing between owner and contractor.
- Split-package – EPCM** – Split of scope into 5-10 EPC lots, with respective responsibility for the supplier of the lots.
 If not covered by one of the package suppliers, the Owner or an EPCM contractor manages technical system integration and overall project management.
- Multiple package – Architect Engineer** – Main packages like nuclear or turbine island are procured using EPC contracts, whereas the rest of the plant is engineered and procured in multiple (>10) packages. The Architect engineer entirely manages engineering and project implementation on behalf of the owner.

